ABSTRACT

Thermo-mechanical stress on vias is reduced, thereby reducing related failures. This can be done by maintaining a via-to-metal area ratio at least as large as a predetermined value below which the additional stress on the vias does not significantly increase.